

Proposal



142 Dale Street, W. Babylon, NY 11704
v: 631 756-9530 f: 756-9537

SUBMITTED TO: LEE PAVONE
Yonkers Public Schools

One Larkin Center
Yonkers, NY 10701
v: 914-376-8008 f: 914-376-8620

DATE: 07/24/18
REVISION: Original
PROJECT: Cornell School – Emergency Abatement and Repair Work
LOCATION: 15 St. Mary's Street
Yonkers, NY 10701

DESCRIPTION OF SALE:

Milcon Construction shall provide all the labor and materials required for the emergency abatement and repair work in Library 34, Art/Music 33, 6th Grade Classroom 32 and 32A, and Storage Room as follows:

1. Removal of approx. 3,250 SF of asbestos ceiling tiles, and approx. 131 asbestos pipe fittings according to all Federal, State, and Local Regulations. Third party air monitoring must be provided by building owner.
2. Clean the existing ceiling grid to remain.
3. Install 24" x 24" Armstrong Cirrus High NRC, Class A ceiling tiles.
4. Reinsulate pipe fittings in the abated locations.

TOTAL PRICE: \$149,000.00

Alternate: Remove and replace asbestos ceiling tiles and pipe fittings in the Corridor and Vestibule area adjacent to the above stated Classrooms – **add \$33,000.00**

Exclusions:

- Performance and Payment Bond.
- Any other work not exclusively described in this proposal

Thank you for your time.

PROPOSAL PREPARED BY: *Boguslaw Kiwior*
Boguslaw Kiwior, Project Estimator

\$149,000
\$33,000
\$182,000 ←
REVIEWED
LP
7/24/18

ACCEPTANCE OF PROPOSAL: The above prices, specifications and conditions are hereby accepted. You are authorized to do the work as specified.

SIGNATURE _____ DATE _____

PRINT _____ TITLE _____