



P.O. Box 1070, Woodridge N.Y. 12789
Phone: 845-434-7805 Fax: 845-434-0307

16 October 2018

Quotation 18.5068.1

Jennifer Hubbard
Yonkers Public Schools
One Larkin Center
Yonkers, NY 10701

RE: Paideia School 15; PBS # 3-801339; Tank # 1 – 6,000 gallon # 2 fuel oil
Tank top repairs

Luzon Environmental Services (Luzon) is a specialty contractor with forty-three years' experience. References can be provided upon request. Thank You for this opportunity for Luzon to provide a proposal.

Luzon will provide all labor, equipment and materials to remove the damaged tank top piping sumps & corroded spill bucket and replace with two new fiberglass watertight tank top piping sumps and a new spill bucket / fill port.

Work To Include:

- Prior to beginning work, perform a tightness test on the tank system to determine if the only damages are to the piping sumps, which were crushed. If the tank system test tight, continue with the repairs.
- Shut down the existing pump set(s) and lock out system.
- Drain down the existing piping and disconnect at the tank.
- Saw cut the blacktop, remove and uncover the tank top.
- Dispose of the blacktop and save the stone for re-use over the tank.
- Carefully disconnect and pull back the piping and tank monitoring equipment at the tank and remove the two piping sumps that are damaged. Save the product piping and electrical for re-use.
- Prepare the tank to receive the two new piping sumps.
- Supply and install two new single wall containment sumps.
- Re-install existing supply and return lines and the electrical conduits with new entry boots and install the existing probe and sensors.
- Supply and install a new spill bucket, with 4" galvanized riser, fill adaptor and cap.
- Re-test the tank & piping system and hydrostatically test the piping sumps and spill bucket for leaks.
- Backfill re-using the existing pea stone that was removed.
- Provide and install new manholes.
- Form and pour an 8" thick, 4,000psi concrete pad with 6 x6 8/8 wwm (takeoff from Roosevelt HS tank pad).
- Patch blacktop around the concrete pad, if necessary.
- Provide a one year warranty on all materials and labor.



P.O. Box 1070, Woodridge N.Y. 12789
Phone: 845-434-7805 Fax: 845-434-0307

Luzon submits the following estimate of costs for the scope of work listed above at the subject property based on the following assumptions:

- If the tank system fails the pre-construction testing a cost of \$ 1,200.00 (primary tank and interstitial testing) will be invoiced and a cost for additional repairs or tank removal/replacement will be provided.
- Labor shall be Westchester County prevailing wages. Certified payrolls will be submitted.
- The only damage is to the piping sumps and no damage to the existing tank. The tank, electrical and piping can be reused.
- The work shall be scheduled to accommodate the school schedule.

Cost:

• Materials	\$ 15,231.00
• Blacktop/concrete disposal	\$ 600.00
• Labor & equipment	<u>\$ 32,509.00</u>
o Total	\$ 48,340.00

JEN:
REVISED FROM \$53,500
- JPC

Payment Terms: As per contract

This proposal is valid for 30 days.

Respectfully submitted,

Robert B. Halprin
President

The undersigned hereby authorizes Luzon Oil Co., Inc. to provide goods and services for the specified work and accepts the terms conditions as set forth.

Authorized Signature: _____ Date: _____

Printed Name and Title: _____