

ATTACHMENT A - BID SHEETS
RECONSTRUCTION OF EXTERIOR ENVELOPE, WINDOWS, DOORS, SITE AND SECURITY AT
WILLIAM BOYCE THOMPSON SCHOOL

BID SCHEDULE #: IFB-6275 ISSUE FOR BID: MAY 4, 2018

YPS PROJECT #10817 SED PROJECT #66-23-00-01-0-302-008

ELECTRICAL & SECURITY - CONTRACT 3

ITEM	APPROX. EST. QUANTITY (A)	ITEMS WITH UNIT BID PRICES WRITTEN IN WORDS	UNIT BID PRICES		TOTAL AMT. BID	
			DOLLARS	CENTS	DOLLARS	CENTS
			(B)		(A) X (B)	
1	1	Lump Sum: Base Bid Price to Complete Electrical and Security Work as Described in the Contract Documents. <u>Two Hundred Eighty-Five Thousand</u> Lump Sum	285,000	00	285,000	00
2	1	Necessary: Miscellaneous Additional Work for Owner Directed Work, if so Desired by the District. <u>Fifty Thousand and -----00/100</u> Necessary	\$50,000	.00	\$50,000	.00

TOTAL BID - ITEMS 1 & 2, INCLUSIVE

Written in Words: Three Hundred Thirty Five Thousand Dollars 00 Cents

Written in Figures: (\$ 335,000.00)

LEGAL NAME OF CONTRACTOR: Fran Corp d/b/a All Bright Electric

ADDRESS: 100 Snake Hill Rd
West Nyack, NY 10994

PREPARED BY: Donna Capone TITLE: Project Executive

TELEPHONE NO.: (845) 358-1200 EMAIL: dcapone@allbrightelectric.com

DATE: 5/4/18

UNIT COST PRICING SHEET - Addendum No. 1 4/18/2018

CITY OF YONKERS - BOARD OF EDUCATION - William Boyce Thompson School - ITB 6275

ELECTRICAL WORK - SECURITY SYSTEM - ADD/DEDUCT FORM

#	Subject	Qty	Description	Add/Deduct - \$Ea (see Types below lines 22-24)		
				Type 1*	Type 2**	Type 3***
1	CCTV CAMERA	1 lot	Furnish, install and terminate CAT-6, average 250' & install CAMERA, INDOOR provided by others	\$ 750	\$ 900	\$ 950
2	CCTV CAMERA	1 lot	Furnish, install and terminate CAT-6, average 250' & install CAMERA, OUTDOOR provided by others	\$ 850	\$ 1000	\$ 1050
3	BURG MOTION	1 lot	Furnish, install and terminate 4/20 (Type "A") cable, average 250' & install MOTION DETECTOR provided by others	\$ 1000	\$ 1100	\$ 1150
4	BURG DE/DSM	1 lot	Furnish, install and terminate 4/20 (Type "A") cable, average 250' & install 3/4" CONCEALED DOOR CONTACT (DC/DSM) provided by others	\$ 600	\$ 725	\$ 775
5	BURG DEVICE	1 lot	Furnish, install and terminate 4/20 (Type "A") cable, average 250' & install BURGLAR ALARM DEVICE SUCH AS: KEYPAD, SIREN, PANIC BUTTON AND ALIKE provided by others	\$ 950	\$ 1100	\$ 1150
6	DOOR DMA/ILDA	1 lot	Furnish, install and terminate 8/20 (Type "D") cable, average 250' & install INTELLIGENT LOCAL DOOR ALARM (ILDA/DMA) and associated 3/4" door contact provided by others	\$ 980	\$ 1130	\$ 1180
7	DOOR ASSY	1 lot	Furnish, install and terminate COMPOSITE (Type "M") cable, average 250' & install CARD READER, CR/DSM, REQUEST TO EXIT (REX) MOTION and wire Electrified Lock provided by others	\$ 1500	\$ 1700	\$ 1800
8	DOOR ASSY	1 lot	Furnish, install and terminate COMPOSITE (Type "M") and 8/20 (Type "D") cables, average 250' & install CARD READER, CR/DSM, REQUEST TO EXIT (REX) MOTION, an ILDA/DMA and wire Electrified Lock provided by others	\$ 2000	\$ 2200	\$ 2300
9	ELECTRICAL/FIBER			Add/Deduct - \$ ea		
10	ELECTRICAL	100	L.F., 600 volt, AWG #12 wire installed in existing conduit or surface metal raceway.			\$ 125
11	ELECTRICAL	100	L.F., 12/2 Metal Clad Cable installed above lay-in ceiling and inside hollow plaster walls.			\$ 320
12	ELECTRICAL	10	L.F., 3/4" Electrical Metallic Tubing installed exposed MAX 15 A.F.F. Including fittings and supports.			\$ 12
13	ELECTRICAL	10	L.F., Metallic Surface Raceway (wire mold #700) surface mount includes all accessories.			\$ 17
14	ELECTRICAL	10	L.F., Metallic Surface Raceway (wire mold #6000) surface mount includes cover and all accessories.			\$ 28
15	ELECTRICAL	1	Ea., 20A Surge Suppression Receptacle Assembly installed surface mount; incl. terminations and 1-Gang box.			\$ 125
16	ELECTRICAL	1	Ea., Furnish, install and terminate CAT-6, average 250' & install Telephone/Data Outlet Assembly (cat 3/cat 6 Trac Jacks) installed surface mount; incl. 1-Gang box.			\$ 375
17	ELECTRICAL	1	Ea., Furnish, install and terminate CAT-6, average 250' & install Telephone/Data Outlet Assembly (cat 3/cat 6 Trac Jacks) installed flush mount in hollow plaster walls; incl. termination and 1-Gang box.			\$ 350
18	FIBER	250'	L.F., 6 strand Fiber SM and Breakout Cable, 50 um including LU termination using LC connectors			\$ 1500
19	CORE	1	Core drill 4" hole in 12" cement			\$ 900
20	CORE	1	Core drill 4" hole in 12" cinder block			\$ 1100
21						
22	TYPE 1*	Cable - installed above lay-in ceiling and inside hollow plaster walls.				
23	TYPE 2**	Cable - installed in 3/4" Electrical Metallic Tubing installed exposed MAX 15 A.F.F. including fittings and supports.				
24	TYPE 3***	Cable - installed in Metallic Surface Raceway (wire mold #700) surface mount includes all accessories.				

CONTRACTOR: Fran Corp d/b/a All Bright Electric
 ADDRESS: 100 Snake Hill Rd
 West Nyack, NY 10994
 BY: *[Signature]* DATE: 5/4/18